



धनगढी उप-महानगरपालिका



नगर कार्यपालिकाको कार्यालय
धनगढी, कैलाली प्रदेश, नेपाल

सुदूरपश्चिम प्रदेश, नेपाल |

दररेट पेश गर्ने सम्बन्धी सूचना

प्रकाशित मिति: २०७९/०५/०९

१. धनगढी उप-महानगरपालिकाद्वारा विभिन्न निर्माण व्यवसायी संग तपसिल बमोजिमको कार्य गर्नका लागि दररेट पेश गर्नका लागि यो सूचना प्रकाशित गरिएको छ।

क्र. स.	विवरण	जम्मा रकम (मु. अ. क. बाहेक)	दररेट पेश गर्ने अन्तिम समय	कैफियत
1	Construction of Drain Slab and Maintenance of Drain Works at Main Road Dhangadhi Kailali	8,83,419.52	(31 st Aug 2022) 2079/05/15 B.S. 05:00 PM	

२. दररेट पेश गर्ने निर्माण व्यवसायीले अनिवार्य रूपमा दररेट पेश गर्ने व्यहोरा सम्बन्धको लिखित निवेदन सहित नवीकरण भएको फर्म/कम्पनी दर्ता प्रमाणपत्रको प्रतिलिपि, नवीकरण भएको व्यवसाय दर्ता (निर्माण व्यवसायी इजाजतपत्र) प्रमाणपत्रको प्रतिलिपि, मु. अ. क. दर्ता प्रमाणपत्रको प्रतिलिपि र आ. व. २०७७/०७८ को करचुक्ता प्रमाणपत्रको प्रतिलिपि संलग्न गरि पेश गर्नुपर्ने छ।
३. उक्त कार्यको लागि आवश्यक BoQ यस कार्यालयको वेबसाइट <http://www.dhangadhimun.gov.np> बाट डाउनलोड गर्न सकिनेछ।
४. BoQ मा आफुले कबोल गरेको रकम अंक र अक्षरमा स्पष्ट बुझिने गरि लेखेर पेश गर्नुपर्ने छ। केरमेट भएको दररेट (BoQ) मुल्यांकनमा समावेश गरिने छैन।

जाति

प्रमुख प्रशासकीय अधिकृत

प्रमुख प्रशासकीय अधिकृत



Dhangadhi Sub-Metropolitan City
Bill of Quantities
Construction of Drain Slab and Maintenance of Drain Works at Main Road Dhangadhi Kailali


 प्रमुख प्रशासकीय अधिकृत

S.N.	Description of Works	Unit	Quantity	Rate (NRs)		Amount (NRs.)
				In figure	In words	
1	Good quality local chimney made Brickwork in 1:4 C/S mortar up to Ground floor in perfect line level finish including supply of materials, wetting the bricks, racking the joints and curing the work for at least 7 days all complete as per approved drawing, Specification and instruction of site engineer.	Cum	17.93			
2	Supplying and laying of 12.5mm thick cement sand plaster in (1:4) ratio on ceiling of good finish including supply of materials, racking the joint, wetting of surfaces & curing the work at least 7days all complete as per approved drawing, Specification and instruction of site engineer.	Sq.m.	26.64			
3	Reinforcement bar of fe 500 grade including supplying, straightening, cleaning, cutting, binding & fixing in position with annealed tying binding wire all complete as per approved drawing, Specification and instruction of site engineer.	Kg	2962.72			
4	RCC works M 20(1:1.5:3) for slab with approved quality of cement, sand and machine crushed stone aggregate including supply of materials, mixing, laying, curing the work at least 7 days etc. all complete as per approved drawing, Specification and instruction of site engineer.	Cum	12.78			
			Total Bidding amount in Nrs.			
				VAT @13%		
			Total Including VAT			

Total In Words:

Stamp of Firm/ Company and Signature of Authorized Person: