

Dhangadhi Sub Metropolitan City
Office of Municipal Executive
Dhangadhi, Kailali
BILL OF QUANTITIES

प्रमुख प्रशासकीय अधिकृत

Name of Work :- Construction of Vermi Compost Pit in Different Ward of DSMC

S.N.	Items	Unit	Quantity	Rate (NRs.)		Amount (NRs.)	Remarks
				In figure	In words		
1	Excavation of all type of soils including disposal (Upto 10m lead & 1.5m lift.).	Cum	7.82				
2	Providing and soling stone in true line and level including filling of voids by local sand all complete as per drawing, specification.	Cum	2.60				
3	75 mm thick Plain cement concrete work in ratio of 1:2:4 cement:sand: coarse aggregate on foundation bed including mixing, laying, compacting and curing of works all complete as per drawing, specification.	Cum	5.64				
4	Providing and laying brick masonry using first class chimney burnt bricks, with cement sand mortar 1:4 including scaffolding, curing, filling, cleaning and racking out mortar joints, making ducts, recesses where required including all materials, labour, lead and lift as per drawing, specification.	Cum	13.86				

Name of Work :- Construction of Vermi Compost Pit in Tarent Ward of DSMC

Handwritten signature

S.N.	Items	Unit	Quantity	Rate (NRs.)		Amount (NRs.)	Remarks
				In figure	In words		
5	12.5 mm thick cement sand plaster work (1:4) including supply of materials, labor, mixing, levelling, curing & scaffolding etc. all complete as per drawing, specification.	Sqm	127.80				
6	Net Cement Puning works over the Screeding works including necessary curing all complete as per the instruction.	Sqm	127.80				
7	Iron Structure Works	Kg	1152.10				
8	CGI Sheet 26 Gauge	Sqm	112.00				
9	CGI plain Sheet Ridge Cover (width 0.9 m)	Rm	16.00				
Sub Total Rs.							
VAT @ 13%							
Grand Total NRs.							

Name of Firm:

Address:

Signature:

Date:

Seal: