



धनगढी उप-महानगरपालिका

नगर कार्यपालिकाको कार्यालय

धनगढी, कैलाली, सुदूरपश्चिम प्रदेश, नेपाल।

दररेट पेश गर्ने सम्बन्धी सूचना

प्रकाशित मिति: २०८०।१२।०५

१. धनगढी उपमहानगरपालिकाद्वारा विभिन्न निर्माण व्यवसायी/फर्म संग क्याम्पसचौक देखि अनाम नगर सम्म रहेका स्ट्रिटलाईटको (२२ थान) स्ट्रिप/रोप लाईट जडान गर्ने कार्यका लागि दररेट पेश गर्नका लागि ७ दिने यो सूचना प्रकाशित गरिएको छ।

क्र.स.	विवरण	जम्मा रकम (मु.अ.कर सहित)	दर रेट पेश गर्ने अन्तिम समय	कैफिकयत
१.	क्याम्पस चौक देखि अनाम नगर सम्म रहेका स्ट्रिटलाईटको (२२ थान) स्ट्रिप/रोप लाईट जडान गर्ने कार्य।	३,३२,३५८।२४	(24 th March 2024) वि.सं. २०८०/१२/११ अपरान्ह ५ बजे सम्म	

२. दररेट पेश गर्ने फर्मले अनिवार्य रूपमा दररेट पेश गर्ने व्यहोरा सम्बन्धको लिखित निवेदन सहित नविकरण भएको फर्म/कम्पनी दर्ता प्रमाण पत्रको प्रतिलिपी, नविकरण भएको व्यवसायको दर्ता (निर्माण व्यवसायीको ईजाजत पत्र) प्रमाण पत्रको प्रतिलिपि, मु.अ.क. दर्ता प्रमाण पत्रको प्रतिलिपि र आ.व. २०७९।०८० को करचुक्ता प्रमाणपत्रको प्रतिलिपि संलग्न गरी पेश गर्नुपर्ने छ।

२. उक्त कार्यको लागि आवश्यक BoQ यस कार्यालयको वेबसाइट <http://www.dhangadhimun.gov.np> बाट डाउनलोड गर्न सकिनेछ।

३. BoQ मा आफुले कवोल गरेको रकम अंक र अक्षरमा स्पष्ट बुझिने गरी लेखेर पेश गर्नु पर्नेछ। केरमेट भएको दररेट (BoQ) मुल्याङ्कनमा समाबेस गरिने छैन।

नरेन्द्र बहादुर खाती

प्रमुख प्रशासकीय अधिकृत

प्रमुख प्रशासकीय अधिकृत

Dhangadhi Sub-Metropolitan City

Bill Of Quantities

Project:- Supply, Delivery and installation of Strip/Rope Light at DSMC Campus Road

In Figure	In Words	Amount (NRs)
8mm width Water proof Strip Light {In 3 Colours of Nepali Flag (Red, Blue & White)}	Standard: ISO Certified Company Strip Size: 8*0.2mm, Input Voltage: 12V/24V DC, Warranty:- minimum 2 years	726
2 Strip Light Driver	Standard: ISO Certified Company Input Voltage: 220 AC Warranty:- minimum 2 years	22
3 Feeder Panel for Lighting control having 50 A DP MCB with 1 nos. 45A contractor, 1 nos. Auto timer, 1 nos selector switch and 1 nos 50 A DP MCB for outgoing.	ISO/IS Standard (MCB Should be C series)	1
4 2.5 sq.mm Multistrand wire.	N/S, IS or ISO Certified	3
5 2X25 sq.mm ABC Cable	N/S, IS or ISO Certified	704
6 ABC Connector	N/S, IS or ISO Certified	44
7 Suspension Clamp with nut-bolts complete set	N/S, IS or ISO Certified	22
8 Waterproof Electric Tape	Nos.	4
9 Binding Wire with insulation	roll.	6
10 PVC Tape	Nos.	20
11 Stringing of 2 core 25 sq.mm ABC Cable all complete work	Mtr.	704
12 Installation of strip/ rope light as instuction by engineer (DSMC smart street light pole-22nos)	set	22
13 Installation of feeder Panel/Control Cabinet including civil foundation and required accessories	set	1
Total Bidding Amount in NRs.		
VAT @ 13%		
Total Amount Including VAT		

Total in Words:

**Stamp of Firm/Company and
Signature of Authorized
Person:**